



Mid Ards Trunk Main – Section F

Contract Value: £760,000
Consulting Engineer: Mulholland & Doherty / McNicholas Construction (Design & Build)
Client: McNicholas Construction Services Ltd
Client's Representative: Declan Carlin (028 9042 4051)
Works completed: October 2007

Categories:- General Civil Engineering, Groundworks & Pipework.

Works Comprised:

- Installation of Dia. 355mm Hep30 Watermain approx. 9.5km within the following sections:-
 - o Approx. 8.5km along Secondary Class Roads
 - o Approx. 1.0km through fields.
- Breaking out of approx. 6,000m³ of rock in trenches along line of the new Mains.
- Construction and installation of associated works including Scour Valves & Chambers, Air Valves & Gate Valves.
- Testing of the mains in 1km lengths – testing up to 12.5Bar



Views showing installation of Dia. 355mm Hep30 watermain in road and across fields.

ASHLEIGH CONTRACTS

30c Ballygelagh Road, Kircubbin, Newtownards, Co. Down BT22 1AE
Tel: 028 4277 2781 Fax: 028 4277 2685