



Dredging at Mullaghmore Harbour, Sligo

Contract Value: €110,000
Consulting Engineer: RPS
Engineer's Representative: Malcolm Brian (028 9066 7914)
Client: Sligo County Council
Client's Representative: Gary Salter (00353 7136210)
Works completed: February 2011

Categories: Marine Civil Engineering, Dredging.

Works Comprised:

- Dredging of approx. 5,000m³ from the harbour area which was undertaken using shore-based plant working from temporary rock bunds to access the 3,500m² area of the harbour and approaches.
- A combination of a 42T Long Reach Excavator and 50T Excavator were used along with 2No A35 Dumptrucks to work on each low tide to retrieve the dredge material and haul to a temporarily stockpile at the head of the Harbour.
- Once the dredge material had dried sufficiently, it was uplifted and hauled approx. 2km from the harbour to a beach where the dredged sand was spread and levelled to a maximum depth of 250mm.



ASHLEIGH CONTRACTS

30c Ballygelagh Road, Kircubbin, Newtownards, Co. Down BT22 1AE
Tel: 028 4277 2781 Fax: 028 4277 2685